DRAFT


DRAFT

DRAFT

DRAFT

DRAFT

## Mixed Waste Landfill Groundwater Monitoring System Comments



Question on Lack of Knowledge on Speed of Groundwater in two Aquifers: Answer pending.

Question on Nickel Contamination in MW1: EPA reviewed the DVD of the video camera log of MW-1. The video clearly indicates corrosion of the stainless steel well screen, which is composed of nickel, chromium, and iron; the metals found in the well's groundwater samples.

FOIA Ex 5 - Deliberative Process

Question on 2 Background Wells Needed, One in each Aquifer: Currently, EPA believes that only one background well is needed in the AF facies, which is considered the uppermost aquifer under RCRA.

Question on using Low Level Tritium Analysis: EPA recommends that a low level tritium

analytical method be used in the future (at least periodically). FOIA Ex 5 - Deliberative Process
EPA recommends using the Low Level with Electrolytic Enrichment (LLEE) method
with detection limits down to about 0.3 pCi/L. This method has been used at LANL for
determining groundwater contamination with great success. FOIA Ex 5 - Deliberative Process
EPA recognizes that the current analytical method is still
protective of the groundwater standard (MCL) of 20,000 piC/L.

Question on Drilling Wells within the Landfill: Monitoring wells are normally located around the perimeter of a landfill. A well inside a landfill would not be part of a monitoring well network to determine if there are releases outside the landfill. Drilling through known contamination will also increase the chances of cross contamination between shallow and deeper zones. Such a well poses a risk of creating a direct conduit for contamination from the surface to the aquifer. RCRA regulations do not require groundwater monitoring within a landfill; rather, the detection monitoring system is to be located at the point of compliance, which is the hydraulically downgradient edge of the unit or waste management area.

Question on Drilling Methods for Well Installation: The preferable drilling method for purposes of ground water sampling is the one that introduces the least amount of foreign matter into the aquifer, for both mechanical (i.e., well damage from pore plugging) and chemical reasons.

Question on Aquifer Characteristics at the MWL: There are two distinct aquifers at the Mixed Waste Landfill, the AF and the ARG. This distinction is evident in the clearly different potentiometric surfaces for the two units. The AF aquifer has very low average hydraulic conductivity (1.81 ft/day) and appears to have some beds with vertical hydraulic conductivity low enough to act as confining beds. FOIA Ex 5 - Deliberative Process

Also, the flow directions are different. The AF aquifer flow direction is to the west-southwest. The ARG aquifer flow direction is the west-northwest.

## FOIA Ex 5 - Deliberative Process

Question on Installing Monitoring Wells in the ARG Aquifer: Additional monitoring wells are not needed in the deep ARG aquifer initially. The "uppermost aquifer" under RCRA is considered the AF facies and is where contamination from the landfill will be found initially. EPA recognizes that the AF facies has very low conductivity and is unlikely to be used for production purposes. FOIA Ex 5 - Deliberative Process

EPA Review of the Borehole Well Videos: EPA reviewed the DVD's of the borehole videos provided by Sandia National Laboratories of monitoring wells BW1, MW1, MW2, MW3, MW5 and MW6. MW1 indicated the most corrosion of the stainless steel screen. MW3 showed much less corrosion, with MW2 and BW1 indicating minimal corrosion. Several of the wells had a brown colored "encrustation like" material on the screen. MW-3 also had a foot long hole in the PVC casing at 40 feet, exposing the annular grout.

Question on the Moats Evaluation: EPA did not review the Moats evaluation due to other factors of the groundwater monitoring system which made the review of that document not pertinent.

Below is EPA's technical evaluation of each monitoring well at the Mixed Waste Landfill.

BW1: This monitoring well needs to be replaced due to the fact that the water levels have dropped to below the screen interval (verified by video log). The replacement well should be located east (hydraulically upgradient) of the mixed waste landfill and screened with a PVC screen across the water table in the AF facies/aquifer.

MW1:

In addition, the well is located mostly upgradient or side gradient of the landfill and is unlikely to detect contamination. A replacement well should be located on the western boundary of the landfill and screened with a PVC screen across the water table in the AF facies.


MW2:

The well is cross gradient from the landfill, so it is unlikely to observe releases from the landfill. The camera video log indicates very little corrosion and this is confirmed by no exceedances of chromium and nickel. EPA recommends this well be used to measure groundwater elevation, unless corrosion problems occur later.

**MW3**:

This monitoring well should be replaced due to some corrosion (much less than MW-1) of the stainless steel screen which is verified by the video camera log and the analytical exceedances of chromium and nickel. Also, the water table has dropped almost below the screened interval. Of note, there is a foot long hole in the PVC casing at 40 feet that appears to be the result of efforts to free jammed equipment. The replacement well should perhaps be moved closer to the unit boundary and should be screened with a PVC screen across the water table of the AF facies.

MW4:



**MW5**:

The intent of this well appears to be monitoring the alluvial fan strata, because the screen is nearly all within that strata. FOIA Ex 5 - Deliberative Process

MW6:

This well is acceptable for monitoring the ARG aquifer, although it's location (not a desirable distance, approximately 500 feet west) is not adjacent to the landfill boundary. MW6 is a good as a control point for helping determine flow directions in that strata. The water level in this well is approximately 15-20 feet above the top of the screen, indicating the confined nature of this aquifer.

Summary, Detection Monitoring Wells Needed: EPA recommends that the Mixed Waste Landfill have three detection monitoring wells at the unit's point of compliance, its western boundary. The wells should be fairly evenly spaced and located to intercept expected potential groundwater releases to the uppermost aquifer, the AF facies.